

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT			1. CONTRACT ID CODE	PAGE OF PAGES
2. AMENDMENT/MODIFICATION NO. <b>0005</b>			J	1   5
3. EFFECTIVE DATE 06-Apr-2004		4. REQUISITION/PURCHASE REQ. NO. W32CS5-4021-0276		5. PROJECT NO.(If applicable)
6. ISSUED BY CODE W912EP USA ENGINEER DISTRICT, JACKSONVILLE PRUDENTIAL OFFICE BLDG 701 SAN MARCO BLVD ATTN: CESAJ-CT JACKSONVILLE FL 32207-8175		7. ADMINISTERED BY (If other than item 6) CODE W912EP BY HAND: DELIVER TO "ISSUED BY" ADDRESS BY MAIL: USAED JACKSONVILLE, PO BOX 4970, ATTN: CESAJ-CT JACKSONVILLE FL 32232-0019		
8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)				X 9A. AMENDMENT OF SOLICITATION NO. W912EP-04-B-0007
				X 9B. DATED (SEE ITEM 11) 27-Feb-2004
				10A. MOD. OF CONTRACT/ORDER NO.
				10B. DATED (SEE ITEM 13)
CODE		FACILITY CODE		
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS				
<input checked="" type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer <input checked="" type="checkbox"/> is extended, <input type="checkbox"/> is not extended.				
Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.				
12. ACCOUNTING AND APPROPRIATION DATA (If required)				
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.				
A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.				
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).				
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:				
D. OTHER (Specify type of modification and authority)				
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input type="checkbox"/> is required to sign this document and return _____ copies to the issuing office.				
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) SHORELINE STABILIZATION PROJECT- VIRGINIA KEY, SECTION 111, DADE COUNTY, FLORIDA  SECTION 00010- SOLICITATION, OFFER AND AWARD  The required response date/time has changed from 09 April 2004 03:00 PM to 16 April 2004 02:00 PM.  SEE CONTINUATION PAGE				
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.				
15A. NAME AND TITLE OF SIGNER (Type or print)			16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
			TEL: _____ EMAIL: _____	
15B. CONTRACTOR/OFFEROR		15C. DATE SIGNED	16B. UNITED STATES OF AMERICA	
_____ (Signature of person authorized to sign)			BY _____ (Signature of Contracting Officer)	
			16C. DATE SIGNED 07-Apr-2004	

EXCEPTION TO SF 30  
APPROVED BY OIRM 11-84

30-105-04

STANDARD FORM 30 (Rev. 10-83)  
Prescribed by GSA  
FAR (48 CFR) 53.243

SF 30 CONTINUATION SHEETS

1. SPECIFICATIONS:

A. Either asterisks appear before and after the line or lines where revisions have been made to the text on the enclosed revised or added pages or the text changes have been updated with additions noted with underlined text and deletions noted with line/cross-outs, and pertain only to changes made by this amendment.

**SECTION 00010A – Supplies or Services and Price/Cost**

Delete page 0001A-3 Supplies or Services and Price/Cost and Replace with the Revised page 0001A-1 Supplies or Services and Price/Cost.

**SECTION 01355:**

a. Change paragraph 3.1.5.1e Endangered Species Protection to read:

3.1.5.1 Endangered Species Protection

e. Manatee Signs

Prior to commencement of construction, each vessel involved in construction activities shall display at the vessel control station or in a prominent location, visible to all employees operating the vessel, a temporary sign at least 8-1/2" x 11" reading, "CAUTION: MANATEE HABITAT/IDLE SPEED IS REQUIRED IN CONSTRUCTION AREA." In the absence of a vessel, a temporary 3' x 4' sign reading "CAUTION: MANATEE AREA" will be posted adjacent to the issued construction permit. A second temporary sign measuring 8-1/2" x 11" reading "CAUTION: MANATEE HABITAT. EQUIPMENT MUST BE SHUTDOWN IMMEDIATELY IF A MANATEE COMES WITHIN 50 FEET OF OPERATION" shall be posted at the dredge operator control station and at a location prominently adjacent to the issued construction permit. The Contractor shall remove the signs upon completion of construction. ~~Sample Manatee Caution Signs are appended to the end of this Section.~~ See Section 3.5 for sample Manatee Caution Signs.

b. Change paragraph 3.1.5.1g Report Submission to read:

g. Report Submission

The Contractor shall maintain a log detailing sightings, collisions, or injuries to manatees occurring during the contract period. The data shall be recorded on forms provided by the Contracting Officer (~~sample Daily Manatee Reporting Log is appended to the end of this Section~~ See Section 3.5 for sample Daily Manatee Reporting Log). All data in original form shall be forwarded directly to Chief Environmental Branch, P. O. Box 4970, Jacksonville, Florida, 32232-0019, within 10 days of collection and copies of the data shall be supplied to the Contracting Officer. Following project completion, a report summarizing the above incidents and sightings shall be submitted to the following:

c. Change paragraph 3.1.5.2 b Sea Turtle Monitoring to read:

3.1.5.2 Sea Turtle Monitoring

b. Daily Visual Inspection

Turtle monitoring activities shall include performance of daily visual inspections of the beach at sunrise by a person permitted by the FF&WCC for handling sea turtle eggs. Any nests discovered shall be excavated and relocated prior to 9:00 a.m. to a nearby self-release beach location where artificial lighting and/or other disturbances shall not interfere with successful incubation, hatching nor hatchling orientation. A log of the results of turtle egg monitoring and recovery activities shall be kept and a copy submitted weekly to the Chief, Environmental Branch, Jacksonville District (~~sample Marine Turtle Nesting Summary Report form is appended to the end of this Section~~ see Section 3.5 for sample monitoring report).

d. Change paragraph 3.1.5.3 a Beach Placement Restrictions to read:

3.1.5.3 Beach Placement Restrictions

a. Equipment Lighting During Sea Turtle Nesting Period April 1 to November 30.

(2) During sand replacement from April 1 through November 30, direct lighting of the beach and near shore waters must be limited to the immediate construction area and must comply with safety requirements. Lighting on offshore or onshore equipment must be minimized through reduction, shielding, lowering, and appropriate placement to avoid excessive illumination of the water surface and nesting beach while meeting all Coast Guard, EM 385-1-1, and OSHA requirements. Light intensity of lighting plants must be reduced to the minimum standard required by OSHA for General Construction areas, in order not to misdirect sea turtles. Shields must be affixed to the light housing and be large enough to block light from all lamps from being transmitted outside the construction area. ~~Refer to beach lighting schematic appended to the end of this Section~~ See Section 3.5 for beach lighting schematic.

e. Change paragraph 3.1.5.3 c. Beach Tilling to read:

c. Beach Tilling

All tilling activity must be completed prior to April 1. If the project is completed during the nesting season, tilling will not be performed in areas where nests have been left in place or relocated. Tilling shall be restricted to the non-vegetated beach area within the project limits.

e. Change paragraph 3.1.5.4a . Monitoring of Construction Area to read:

3.1.5.4 Protection of Migratory Bird Species

a. Monitoring of Construction Area

In order to meet these responsibilities, the Contractor shall conduct monitoring of the construction area beginning 1 April through 31 August, if construction activities occur during that period. Daily monitoring using the Daily Bird Monitoring Report shall be conducted during the dawn or dusk time frames by a bird monitor approved by the Contracting Officer. (Caution shall be taken by the monitor to avoid disturbance to the nesting birds.) The Contractor shall maintain a daily log detailing monitoring and nesting activity (not all bird species are listed). ~~Sample monitoring report and qualification sheet are appended to the end of this Section~~ See Section 3.5 for sample monitoring report. Within 30 days after completion of construction, a summary of monitoring shall be submitted to the Corps detailing nesting and nesting success/failure including species, number of nests created, location, number of eggs, number of offspring generated during the project and reasons for nesting success or failure, if known.

## SECTION 02391:

a. Change paragraph 3.4.2b to read:

b. The ~~excavated borrow~~ material shall be placed and brought to rest on the beach to the lines, grades, and cross section indicated on the drawings, unless otherwise provided for herein or directed by the Contracting Officer. The beach is subject to changes and the elevations on the beach at the time the work is done may vary from the elevations shown on the drawings. The Contracting Officer reserves the right to vary the width and grade of the berm from the lines and grades shown on the plans in order to establish a uniform beach for the entire length of the project. The beach fill cross sections shown on the drawings are for the purpose of estimating the theoretical amount of fill needed and will be used by the Contracting Officer in making any change in the lines and grades. The Contractor will not be required to dress the fill below the mean high water to the slopes shown but will be required to do the dressing specified in subparagraph "Dressing for Payment" below.

a. Change paragraph 3.4.7 to read:

3.4.7 Work Area

The construction easements ~~and borrow area limits~~ available to the Contractor for accomplishing the work are shown on the drawings. The contractor shall allow access for others to work at the nursery or exclude it from the construction area fencing. At the fill site, The Contractor may only operate within the work areas shown on the drawings. The Contractor shall exclude the public from the work areas in the immediate vicinity of his excavating, transporting, stockpiling, and disposal operations.

2. **DRAWING CHANGES:** The following are descriptive changes to the drawings. Drawings should be adequately marked to indicate that they have been changed:

Drawings No. 2/1 Zone D-1. Add at proposed Groin No. 25: Contractor's Limit of Work. West Limit – Proposed Groin No. 25

Drawings No. 2/2 Zone D-4, 5. Add at Station 0+00: East Limit of Work. East Limit – Station 0+00.

(End of Summary of Changes)

## SECTION 00010

## SUPPLIES OR SERVICES AND PRICES/COSTS

## VIRGINIA KEY SHORELINE STABILIZATION PROJECT, DADE COUNTY, FLORIDA

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT
0001					
0001AA	PRE- AND FINAL CONDITION SURVEYS	1	LUMP SUM	\$ _____	\$ _____
0001AB	DEBRIS REMOVAL (ESTIMATED QUANTITY)	2.1	ACRE	\$ _____	\$ _____
0001AC	REMOVAL OF CONCRETE KING PILES AND TIMBER PANELS (ESTIMATED QUANTITY)	192	LINEAR FEET	\$ _____	\$ _____
0001AD	REMOVAL OF TIMBER GROINS (ESTIMATED QUANTITY)	1,272	LINEAR FEET	\$ _____	\$ _____
0001AE	CONSTRUCTION OF TIMBER GROINS (ESTIMATED QUANTITY)	1,290	LINEAR FEET	\$ _____	\$ _____
*0001AF	BEACH FILL FROM BORROW MOUNDS (ESTIMATED QUANTITY)	1,500	CUBIC YARD	\$ _____	\$ _____
*0001AG	SAND DUNE FILL FROM BORROW MOUNDS (ESTIMATED QUANTITY)	500	CUBIC YARD	\$ _____	\$ _____
0001AH	TURBIDITY MONITORING	1	LUMP SUM	\$ _____	\$ _____
0001AJ	BEACH FILL TILLING	1	LUMP SUM	\$ _____	\$ _____
0001AK	SEA TURTLE MONITORING	1	LUMP SUM	\$ _____	\$ _____
0001AL	MIGRATORY BIRD MONITORING	1	LUMP SUM	\$ _____	\$ _____
0001AM	DISPOSAL OF CONCRETE KING PILES INTO BRICKELL OFFSHORE SITE	1	LUMP SUM	\$ _____	\$ _____
(LINE ITEMS 0001 THROUGH 0001AM):					\$ _____

NOTES: (1) BIDDERS MUST PROVIDE A BID ON ALL LINE ITEMS. SEE PROVISION AT 52.248-18 (SECTION 00100).

(2) SEE SECTION 00100, "INSTRUCTIONS TO OFFERORS, EVALUATION FACTOR FOR AWARD"

(3) FAILURE TO COMPLETE AND RETURN ALL REQUIRED SUBMISSIONS (SF 1442, SECTION 00010A, SECTION 00600 AND BID BONDS) COULD RENDER YOUR BID NONRESPONSIVE.